

June 30th, 2022

IMPORTANT NOTICE
EFFECTIVE IMMEDIATELY & EXPIRING ON 12/31/23
REVISED AND EXPANDED PART 2

Subject: **Provisionally approved meter sockets and CT enclosures for use in Atlantic City Electric, Delmarva Power & Light and PEPCO service territories.**

To: Electric Utility Customers, Contractors and Suppliers.

Electric equipment suppliers and contractors across the PHI's service territories continue to report shortages of PHI approved meter sockets and CT cabinets needed to complete construction of electric service projects. In response to these ongoing shortages, PHI has provisionally approved several self-contained meter sockets, pedestals and CT cabinets that will be acceptable for installation for a limited time.

These provisional approvals will expire at the end of 2023 (Date 12/31/2023). These meter socket types will be further evaluated for future inclusion on the PHI Approved Meter Equipment list. Permanent approval necessitates standardization to the PHI design requirements including, horn bypass, PHI sticker, etc. that may also necessitate new part numbers.

Note: All ACE and DPL approved sockets are now provisionally approved for installation in the PEPCO region. Lay in lugs are now provisionally permitted in Pepco

Note: Due to the nature of provisional approval, it is the contractors/customer's responsibility to ensure that the meter socket selected is correct for the application (OH/UG, knockout/hub placement, 5th jaw, etc.). A factory installed 5th jaw must be in place for all 120/208V single-phase services and anti-inversion clip must be installed for all 320A sockets.

The following meter sockets and CT cabinet types are now provisionally PHI approved.



SIEMENS/TALON

- Cat # **UAT417-PPQG**
- Cat # **UAT417-0GF**
- Cat # **UAT417-0PRG**
- Cat # **UAT417-PG**
- Cat # **UAS877-PPZA**
- Cat # **UAT417-0P**
- Cat # **UAT417-XPQG**
- Cat # **48104-82WI** (Anti-inversion clip required)
- Cat # **47604-02CV**

New additions – 6/30/22 (*)

- Cat # **40407-02JM ***

EATON COOPER/CUTLER HAMMER

New additions – 6/30/22 (*)

- Cat # **UAT417 *** (Any socket starting with UAT417)
- Cat # **USA:JC0406L1200RHJB ***
- Cat # **SUAT317-0G ***
- Cat # **MM0202S1200RJB ***
- Cat # **MM0406L1200RHJB ***
- Cat # **MM0202B1200RJBX ***
- Cat # **MB48B200BTSG**
- Cat # **UHTTRS202BCH**
- Cat # **UFHTRS213CCH**
- Cat # **UGHTRS223ACH**
- Cat # **MM0202B1200RJB ***
- Cat # **MM0202B1200R ***
- Cat # **MM0202B1125R ***
- Cat # **MM0202B1150R ***

MILBANK

- Cat # **S8930-XL-PEP**

New additions – 6/30/22 (*)

- Cat # **U7040 *** (Any socket starting with U7040)
- Cat # **U1252 ***
- Cat # **U8173-XL-KK-BLG ***
- Cat # **U7021-RL-KK-BL ***
- Cat # **U5168-XTL-200 ***
- Cat # **U5168-XTL-200-KK-5T-PEP ***
- Cat # **U5168-XTL-200-KK-5T-DPL ***
- Cat # **U5897-RL-200-KK-PEP ***



RONK

New additions – 6/30/22 (*)

- Cat # **MSB200HA ***
- Cat # **MSB200HA-UG ***

RAYCAP

New additions – 6/30/22 (*)

- Cat # **RMS-BL5-xAE ***

MILBANK PEDISTALS

New additions – 6/30/22 (*)

ACE & DPL Only Pedestals:

- Cat # **CP3B921*****DPL ***
- Cat # **CP3B541*****DPL ***
- Cat # **CP3B52B*****DPL ***
- Cat # **CP3B528*****DPL ***
- Cat # **CP3B922*****DPL ***
- Cat # **CP3B542*****DPL ***
- Cat # **CP3B525*****DPL ***

PEPCO Only Pedestals:

- Cat # **CP3B521*****PEP ***
- Cat # **CP3B541*****PEP ***
- Cat # **CP3B528*****PEP ***
- Cat # **CP3B522*****PEP ***
- Cat # **CP3B542*****PEP ***
- Cat # **CP3B525*****PEP ***

CT CABINETS:

Any CT cabinet that meets the following requirements are acceptable for installation. CT cabinets must be of metal construction, have a ¾” plywood backboard and be NEMA 3R rated. The CT cabinets must also have hinged type door that swings open horizontally (No lift-off/up covers) with provisions for padlock installation.

- 400 through 1200 Amp at least 36” W x 32” H x 13” D
- 1600 through 2000 Amp at least 40” W x 36” H x 13” D

As previously stated, this provisional equipment approval is effective immediately and will expire on December 31st, 2023.